



**Town of Cape Carteret
102 Dolphin Street
Cape Carteret, NC 28584
252-393-8483**

**INVITATION TO BID
REPLACE STORM DRAINAGE
YAUPON AND NEPTUNE DRIVE**

You are invited to submit a firm price bid on the storm drainage on Yaupon and Neptune Drive.

While cost is always an important factor in any project, public or private, your bid proposal won't necessarily be selected based on cost alone. The successful bidder will be selected based on the overall best value as perceived by the Board of Commissioners (BOC).

Attached is the project information. I have scheduled a mandatory meeting to be held on Wednesday, May 26, 2010 at 9:00 a.m. at the Cape Carteret Town Hall to review the bid information, answer questions, and provide a tour of the job site. This will provide you with a firsthand introduction to our proposed project.

Your bid proposal should be received in a sealed envelope by the Town Clerk, Town of Cape Carteret, 102 Dolphin Street, Cape Carteret, NC 28584 no later than June 14, 2010 at 2:00 PM. You will be informed if you are the successful bidder following the regular Meeting of the Board of Commissioners the week of June 21st.

If you have any questions please do not hesitate to call me. Thank you for your interest in our project and I look forward to meeting with you.

Sincerely,

Mark Parrish
Commissioner
(252) 241-4379

TOWN OF CAPE CARTERET
102 DOLPHIN STREET
CAPE CARTERET, NC 28584
252-393-8483

The Town of Cape Carteret will be taking bids for the following project:

Replacement of Storm Drainage-Yaupon and Neptune Drives

The project consists of approximately:

Base Bid

1. 67 linear feet of 18" reinforced concrete pipe replacement crossing Yaupon Drive from drop basin to drop basin.
2. 410 linear feet of 18" reinforced plastic pipe from Yaupon Drive drop basin to Neptune Court Drop Basin. This will include installation of town furnished drop basin.
3. 65 linear feet of 18" reinforced concrete pipe crossing Neptune Drive from drop basin to drop basin.

Alternate # 1

1. 35 linear feet reinforced concrete pipe replacement crossing Neptune Court drop basin to drop basin.

Alternate #2

1. 342 linear feet reinforced plastic pipe replacement along the western side of Neptune Court drop basin to drop basin.

All existing drop basins will be utilized.

All existing site conditions shall be in like condition upon completion including turf and driveways. (Seeding and gravel will not be acceptable)

NC DOT Standards for Roadways will apply to all aspects of this project.

General Contractor shall verify and locate all utilities prior to any construction.

A mandatory pre-bid site visit will be held on Wed. May 26, 2010 at 9:00 AM at the Town Hall.

Bids will be accepted until 2:00 pm, June 14, 2010 and will be opened at that time.